Methane mitigation achievement, including agriculture, is crucial to limiting dependence on uncertain carbon dioxide removal in national carbon budgeting equitably meeting Paris goals

Paul R PRICE^{1#*}, Barry MCMULLIN¹, Aideen O'DOCHARTAIGH¹

¹Dublin City University, Dublin 9, Ireland *Corresponding Author, <u>paul.price@dcu.ie</u>, *Presenting Author

Abstract – Developed nations are likely to overshoot their "fair share" of a remaining global carbon budget (rGCB) equitably aligned with meeting the Paris Agreement (PA) temperature goal. PA-aligned pathways in integrated assessment modelling typically rely on large scale carbon dioxide removal (CDR), even though such reliance is highly uncertain and likely inequitable. Moreover, radical reductions in fossil fuel combustion (FFC) cut CO2 emissions but result in a parallel reduction in cooling aerosols, severely reducing the available rGCB. Consequently, substantial land use change (LUC) CO₂ and agricultural non-CO₂ mitigation is now crucial to achieve global carbon budget outcomes aligned with meeting the stringent Paris temperature goal. However, most negative emissions literature undervalues or ignores the importance of early, sustained, and permanent methane (CH₄) in equitable mitigation limiting CDR dependence. Therefore, to meet a national PA "fair share" temperature goal, we use the recently developed GWP* CO₂ warming equivalence method in illustrative scenarios to assess trade-offs between: mitigation of CO₂ and N₂O; and temperature impact reduction (TIR), via CH₄ mitigation and limited CDR. Ireland provides an informative, developed nation case study due to: carbon budgeting law and policy; rising agricultural CH₄ and N₂O emissions; and net emissions of LUC CO₂, due to drained organic soils, ongoing peat extraction, and declining forestry CO₂ removals. Practically, Ireland's CDR potential may be only 200 MtCO₂. Based on the IPCC database scenario sets for 1.5C low overshoot and Lower 2C, GWP* is used to benchmark a "prudent" multi-gas rGCB* of 640 GtCO₂we for CO₂+N₂O+CH₄ from 2015. Ireland's population-based share of this is a multi-gas national carbon quota (NCQ*) of 410 MtCO₂we, depleting from 2015 onward. Using a spreadsheet tool, illustrative scenarios are assessed for different CO₂+N₂O+CH₄ reduction pathways over time. Only radical scenarios, achieving net zero CO₂ before 2050 while permanently cutting CH₄ by 50%, limit overshoot and enable a return to the Paris-aligned national quota by 2050 without exceeding the practical CDR limit to 2100. Key findings include guidance on use of GWP* in mitigation analysis, the certainty-importance of early and deep CH₄ mitigation in addition to rapid CO₂ reduction to limit CDR reliance. Given mitigation delay, the need for immediate and deep CO₂ and CH₄ mitigation is confirmed, requiring regulatory limits on GHG-intensive agriculture and land use activities as well as radical reductions in fossil carbon combustion for energy and cement use.

1 Introduction

1.1 Prudence and equity consideration in meeting the Paris temperature goal

The Paris Agreement [1] Article 2 objective – linking limiting global warming to "well below 2°C" and 'pursuing efforts to limit global average temperature to 1.5°C above pre-industrial levels' – can be considered as a single goal [2], referred to as 'the long-term temperature goal' in Article 4. Also under Article 2, the UNFCCC Parties have agreed to achieve this goal through actions 'implemented to reflect equity and the principle of common but differentiated responsibilities and respective capabilities [CBDR-RC], in the light of different national circumstances'. Therefore, any assessment of "fair share" climate action by an individual Party requires a clearly defined CBDR-RC approach, applicable across all nations, setting out a justification for all quantitative and normative parameter choices being made toward meeting the temperature goal prudently and equitably [3], [4]. Even if met, as of 2022 existing Party commitments are collectively only sufficient to limit to just below 2°C, falling well short of the PA goal unless additional action is achieved starting immediately [5]. The IPCC Sixth Assessment Report's three working group (AR6-WG) summaries for policymakers (SPMs) [6]–[8] set out the extreme urgency of climate action required to meet the more prudent 1.5°C target with limited overshoot, even allowing for only a 50% probability of success. Achieving the PA temperature goal on a global CO2-only basis can be quantified scientifically as a remaining global carbon budget (rGCB) from a stated base year. In the IPCC AR6-WGI SPM a central rGCB value of 500 GtCO₂ from the beginning of 2020 is given for a 50% probability of limiting further global temperature rise to 1.5°C [6], assuming given stated uncertainties and defined non-CO₂ emission pathways, particularly for methane (CH₄) and nitrous oxide (N₂O). However, given "main case" median assumptions for non-CO₂ and other parameters [9] finds a 17% chance that the rGCB for 1.5°C had already been exceeded by the start of 2020.

1.2 Equivalent temperature impact reduction (TIR) via CDR or CH4 mitigation

Non-CO₂ emissions have a substantial effect on the rGCB value and warming [10] such that IPCC illustrative CO₂ pathways limiting to 1.5°C with low overshoot or to "well below 2°C" rely on median total emission reductions by 2050 relative to 2020 of over 50% for CH₄ and ~20% for N₂O (Fig. SPM.5a in [8]). The warming-to-date due to long-lived climate forcers (LLCFs), primarily CO₂ but also N₂O, continues to increase while their combined annual net CO₂eq emissions are above net zero, whereas the total warming-to-date due to short-lived climate forcers (SLCFs), like CH₄, can decline in future if rates of SLCF annual emission are reduced substantially and permanently. Consequently, in mitigation scenarios, "temperature impact reduction" (TIR) can be achieved by CDR *or* by an equivalent reduction in annual CH₄ emissions rate [11]. Given the escalating difficulty of meeting the Paris goal [12], rapid CH₄ mitigation has increasing TIR value, and hence, echoing WGI, the AR6-WGIII SPM states:

'Deep GHG emissions reductions by 2030 and 2040, particularly reductions of methane emissions, lower peak warming, reduce the likelihood of overshooting warming limits and lead to less reliance on net negative CO_2 emissions that reverse warming in the latter half of the century.' [8]

However, in contrast with this increased IPCC emphasis in AR6 on the importance of CH₄ mitigation, the draft full WGIII report's CDR assessment (Ch. 12.3) emphases reliance on TIR from development of CDR as an offset for residual GHGs on a GWP₁₀₀ basis, without acknowledging the substantial TIR potential of immediate CH₄ mitigation to ease near-term mitigation or overshoot, and to limit long-term CDR reliance. Reflecting the Ch. 12.3 CDR emphasis on GWP₁₀₀ assessment, the WGIII SPM states:

'The deployment of CDR to counterbalance hard-to-abate residual emissions is unavoidable if net zero CO_2 or GHG emissions are to be achieved. The scale and timing of deployment will depend on the trajectories of gross emission reductions in different sectors.' C.11 in [8]

Globally, the importance of CH₄ mitigation for TIR is evident in IPCC illustrative modelling of CO₂ pathways aligned with the PA goal, which are reliant on deep reductions in CH₄ as well as on CDR, as is shown in: SR15 Figure SPM.3; AR6-WGI Figure.SPM.4 SSP1-[1.9 and 2.6] illustrative pathways; and in AR6-WGIII Figure SPM.5, most particularly in the deepest CH₄ reductions shown for the illustrative mitigation pathway IMP-SP from 2020, which focuses on shifting pathways toward global sustainable development, including significant dietary change away from animal food production and consumption. In the 1.5°C IMP-SP scenario CDR reliance is minimal. In research examining alternative pathways to 1.5°C with limited CDR requirement [13] includes a low non-CO₂ scenario with the following GHG cuts up to and sustained beyond 2050: for CH₄, 'ruminant enteric fermentation in ruminants 73%, sewage 95%, landfills 100%, animal waste/manure 100%'; N₂O, 'emissions reductions are set at fertilizer use 80%, animal waste/manure 75%'; and for fluorinated gases, 97%.

1.3 Questioning "hard-to-abate" assertions in sectoral CDR policy reliance

The AR6-WGIII IMP-SP and literature pathways assessing radical GHG reductions through combined regulatory action and demand reduction indicate they are at least possible and therefore achievable with directed policy. This directly challenges the AR6-WGIII assertion that sectors such as aviation, heavy industry, and animal agriculture can be simplistically characterised as "hard-to-abate". Furthermore, the Paris goal importance of agricultural non-CO₂ forcing changes and land use change (LUC) CO₂ removals are made apparent in the scenario finding described by Mengis and Matthews in [14] which

'indicates clearly that focussing only on fossil fuel emissions reductions, without also mitigating LUC-related CO₂ emissions and non-CO₂ GHG from LUC and agriculture, would likely result in an impossibly small remaining fossil fuel carbon budget for the 1.5 °C target' [14]

This understanding, which can be extended to Party-level carbon budgeting under the good faith and fair share principles underpinning national PA commitments [3], shows that it is misleading, and may result in mitigation deterrence [15], [16], to assume simplistically that agriculture or aviation or other emissions are necessarily "hard-to-abate". However politically difficult it may be to abate such high GHG sectors, they may *need* to be abated to meet a Party's fair share target given the PA's 'binding obligations of conduct coupled with a good faith expectation of results' [17] in delivering sufficient climate action and in the context of relevant

legal principles for national fair share effort [3], [18]. (The UK FIRES Absolute Zero report [19] indicates highly restrictive pathways on aviation and animal agriculture emissions are required due to insufficient technical mitigation.) Therefore, the phrases "hard-to-abate" or "hard-to-transition" can be misleading as they *incorrectly* imply: (1) quantitatively, that individual GH gases or sector-total GHGs can be meaningfully equated on a GWP₁₀₀ basis to assess warming impact; and (2) normatively, that existing GHG intensive activities continue unchecked if only costly technical measures are assessed to address them. The latter issue is especially apparent in the IPCC evaluation of mitigation for agriculture in AR6-WGIII, for which Table 7.3 in [20] indicates that only estimates of technical mitigation measures have been assessed and "no data" is available for IAMs for demand-side measures. This means that the large residual agricultural CH₄ seen by 2050 in IAMs occurs because mitigation of ruminant and manure CH₄ is found to be *technically* costly, and yet policy and regulatory options that may be less *societally* costly than non-agriculture mitigation or CDR have not been assessed.

In this article, using coarse-grained assessment for a developed nation, we evaluate this "hard-to-abate" framing at the individual Party level by presenting alternative scenarios meeting the same PA-consistent fair share GHG quota by 2100. The methodology enables scenarios to show by-gas and aggregate pathways to examine trade-offs between LLCF gross emissions and TIR (from differing combinations of CH₄ mitigation CDR), within a context of limited assessed national CDR potential. Crucially, we assess the temperature impact of scenarios, using the GWP* method in coarse-grained modelling, rather than depending only on GWP₁₀₀ equivalence, which does not show the substantial near- and medium term TIR mitigation opportunity available through reducing a Party's annual CH₄ emissions rate. The results indicate that agricultural sector emissions can only be sufficiently abated by substantially reducing ruminant-derived food production.

1.4 Assessing CDR and CH₄ in PA mitigation using temperature impact modelling

Suggested CDR methods aiming to limit net emissions or to achieve a period of net negative emissions, globally or at Party level, include 'anthropogenic activities that remove CO₂ from the atmosphere and store it durably in geological, terrestrial, or ocean reservoirs, or in products' as described in AR6-WGIII section 12.3 [20] and as shown in the CDR taxonomy in its Cross-Chapter Box 8, Figure 1. Serious concerns are expressed in this section regarding reliance on CDR at scale, including the risk that they may not be achieved at the scale required, citing [34], [35], and that any assumption of CDR at large scale may deter more immediate or certain mitigation of GHGs. This AR6-WGIII section notes that in globally limiting to a temperature goal or to achieve global TIR after overshoot, different nations could follow different pathways that add up to these outcomes. The discussion in this CDR-focused WGIII section advocates

achieving net zero GHG implies gross CO_2 removals to counterbalance residual emissions of both CO_2 and non- CO_2 gases, applying GWP_{100} as the metric for reporting CO_2 -equivalent emissions, as required for emissions reporting under the Rulebook of the Paris Agreement [20]

However, this quote references a Ch. 2 discussion in Cross-Chapter Box 2 GHG emission metrics that notes that rapidly cutting emissions of short-lived climate forcers (SLCFs)

including CH₄ have greater climate benefits than if weighted by GWP₁₀₀, so it does not make sense to counterbalance declining CH₄ with CDR simplistically on a GWP₁₀₀ basis. Even if GWP₁₀₀ reporting is required for PA Rulebook reporting, *temperature impact* modelling of bygas societal and sectoral pathways in line with equitably meeting the accepted *temperature* target can still be used informatively to show corresponding GWP₁₀₀ trajectories to assess policy options or regulatory action.

As confirmed by [14] and summarised in AR6-WGIII (Box TS.2 in, [8]) the TIR effect of sustained CH₄ reductions has been shown to be equivalent to CDR in terms of a one-off CDR, as can be estimated by use of the GWP* [36]-[38] or CGTP (Combined Global Temperature Change Potential) [39] approaches to determine changes in cumulative CO₂ warming equivalent (CO₂we) from a given start year. These methods have commonly been described as GHG equivalence step-pulse "metrics" but it is more accurate to describe them as coarsegrained 'micro climate models (MCMs)' [40] useful in assessing temperature impact on the basis of readily available or projected time series of by-gas mass emissions (or equivalent CO₂eq data). It is important to understand annual GWP* or CGTP values are not directly comparable with the annual GWP₁₀₀ CO₂eq values, so they are not directly useful to assess current action on mass emissions (for which GWP₁₀₀ is a useful linear proxy) or as a metric for UNFCCC inventory reporting [40] and simplistic use of these method could result in inequitable outcomes [41] unless a PA CBDR-RC context is clearly defined. In this article this is achieved by first assessing a global multi-gas rGCB* from 2015 as a common basis for burden sharing so that all nations have an identical per capita share from a benchmark 2015 base year.

1.5 Ireland: a case study of CH₄ and CDR reliance in meeting the Paris goal

Ireland provides an informative case study of the effects and importance of including non-CO₂ emissions in climate mitigation assessment relative to the PA goal because it has an unusual emissions profile of high CH₄ and N₂O per capita. 93% of each of these GHGs is related to agriculture, primarily from farm production of milk from dairy cows and meat from livestock. Moreover, Ireland's climate governance is also notable in having amended its climate Act in 2021 to institute a programme of 5-year carbon budgeting on a cumulative CO₂eq basis that is required to be 'consistent with' PA Articles 2 and 4(1).

Following passing of the amended Act, national budgets of 295 MtCO₂eq and 200 MtCO₂eq for 2021–2025 and 2026–2030, as well as a provisional 2031–2035 budget, were first recommended by the independent Climate Change Advisory Council (CCAC) in a Technical Report in October 2021 [42] (hereafter denoted as *CCAC-TR*). Subsequently, in April 2022 the first two society-wide 5-year carbon budgets were confirmed by the Irish parliament, the Oireachtas, and then, by the end of June 2022, the government is to propose constituent legally binding *sectoral ceilings* – for power generation, industry, transport, buildings, agriculture and waste. In its assessment of carbon budgets the CCAC defined five *core scenarios* – on a simplified basis of "Agriculture", as a proxy name for non-CO₂ mitigation by 2030, and corresponding "Energy" (CO₂) mitigation levels – calculated to meet the approximately the same overall 10-year CO₂eq budget up to 2030 and for 2020–2050. The CCAC-TR scenarios were based on Agriculture mitigation by 2030 of 19%, 26%, 33%, 40%, and 51%, resulting in

corresponding scenario Energy CO_2 reductions of 69%, 65%, 61%, 57%, and 51%, respectively. CH_4 and N_2O are assumed to be reduced by the same stated scenario "Agriculture" rate up to 2030. Net CO_2 emissions reach net zero in CO_2 eq terms by 2050 at latest. Notably, using a form of GWP*, the CCAC-TR Figure 4-3 indicates that it is the differences in CH_4 mitigation that result in a much larger variation in estimated temperature impact across scenarios than N_2O or CO_2 mitigation differences.

To inform Ireland's current national policy discussion in advance of agreeing sectoral ceilings, this article focuses on and contrasts "Agriculture" scenarios that reduce CH₄ and N₂O by 10%, 22% and 30%, by 2030, as well as an additional deeper non-CO₂ mitigation scenario to align action with meeting the PA goal by 2050. As Ireland's climate Act requires that the carbon budgeting programme is consistent with the temperature goal, as described under the Methods (2.1), we assess a multi-gas 1.5°C rGCB* for [CO₂+N₂O+CH₄] that is then allocated on an equal per capita and population CBDR-RC basis to give a "minimally equitable", multi-gas national carbon budget (NCQ*). Informed by current policy discussion and using a spreadsheet tool, coarse-grained scenarios are then applied according to a consistent scenario definition method, to define and assess pathways that meet the temperature target NCQ* quota level by 2100 at latest but ideally by 2050.

Although global pathways minimising 1.5°C overshoot have been intensively examined using climate models [5], [20], developed nation overshoot scenarios have not, therefore the methodology applied in this article contributes an informative methodology for analysis of national mitigation choices that is readily applicable to other Parties. Such analysis informs understanding of crucial fair share mitigation issues for developed Parties that has not been widely understood. This includes differentiating reaching an *overshoot net zero* (ONZ) – corresponding to a level of "no further warming" but at peak carbon debt [43] – from achieving *quota net zero* (QNZ), stabilising at the target NCQ* level after cancelling any carbon debt. This distinction is important because recent grey literature climate policy briefings often confusingly and misleadingly suggest that a "no further warming" ONZ for a Party is an appropriate climate action goal when, logically it is only reaching an equitable QNZ without any overshoot carbon debt that can be assessed as being consistent with Paris Article 2 and the subordinate Article 4(1). Given that the PA and UNFCCC are predicated on action by national or regional Parties, such claims are even more misleading when incorrectly asserted as a meaningful goal for an individual sector or corporate entity.

In the context of equitable 1.5°C carbon budgeting whereby urgently required rapid fossil fuel CO₂ reduction is becoming insufficient to avoid PA target overshoot, this article contributes to climate mitigation literature by clarifying important trade-offs between: TIR achieved more certainly and more quickly through agricultural and fossil CH₄ mitigation; and, TIR achieved less certainly and more slowly by CDR such as BECCS that may not deliver at scale [44], or through land-based soil [45] for or forestry CDR that are inherently of limited mitigation value [46] due to uncertainty, impermanence, saturation and additionality issues [47]–[50].

2 Methods

2.1 Assessing multi-gas remaining global GHG budget and a derived Party "fair share"

In the research for this article the GWP* method is used as described in Ch. 7 of [51], and in greater detail in [52], to assess the remaining global GHG budget, denoted rGCB*, in cumulative CO₂we on a combined [CO₂+N₂O+CH₄] multi-gas basis from 2015. Assessed rGCB* values from 2015 are based on the IAM 1.5C low overshoot and Lower 2C scenario-set sampling of possible climate model temperature outcomes. Respectively, corresponding to the PA goal, using the 50th percentile 1.5C low overshoot results for 1.5°C gives an rGCB* of 640 GtCO₂we; and using the 10th percentile Lower 2C results for "well below 2°C" gives an rGCB* of 1030 GtCO₂we. Acknowledging the inherent grandfathering and inequity in any "fair shares" approach [4], as set out in [43] we argue that 2015, the year of the global political commitment to the PA, is the latest possible start date for an analysis of Paris consistency and that a prudence level of a 50% chance of 1.5°C is a reasoned basis for a "minimally equitable" PA fair sharing among Parties. This benchmark level results in a maximum remaining emissions quota for developed Parties with high per capita emissions because choosing an earlier year or using more stringent criteria would result in a relatively smaller remaining budget. (Given the rationale in [43], choosing a later year would require referenced and normative justification. For example, although the CCAC-TR "Paris Test" used the base year stated in IPCC AR6, no such basis for CBDR-RC fair sharing is ever advocated by IPCC reports so a recent year cannot be simply used as a base year without additional referenced justification.)

As it is simply defined and is aligned with principles of international environmental law [3] – unlike inertia, least cost or convergence – we then use equal per capita sharing of the 1.5°C 50th percentile rGCB* from 2015 on a national population basis (defined as the 2015 equal per capita rGCB* share multiplied by 2015 national population) to define a national fair share GHG quota (NCQ*). This is then the PA-consistent target corresponding to their temperature impact share of the remaining warming up to 1.5°C without overshoot with a 50% likelihood. In this approach therefore, all UNFCCC Parties are allocated a cumulative NCQ* CO2we total for [CO₂+N₂O+CH₄] on the same equal per capita global basis at the start of 2015. For each Party this is adjusted by the annual emissions from then onward based on cumulative CO₂we emissions calculated using GWP*. For Ireland the NCQ* values derived from the 2015 rGCB* values are 410 MtCO₂we for 1.5°C and 660 MtCO₂we for "well below 2°C". As noted, using this minimally equitable approach simply benchmarks comparative action on a multi-gas basis from 2015, its use does not imply that high emitting nations can avoid identifying additional actions - to partially defray prior historic responsibility or accepting their greater relative capacity for mitigation action - in order to to mitigate unfair biases in climate action against poorer nations [53]. Clearly, explicitly defining the parameters for a national "Paris Test" of society-wide carbon budgeting is therefore important to assess national or regional Party scenarios relative to alignment with the Article 2 temperature goal and equitable implementation. As countries to date have made only limited statements regarding equity [54] and more will be required for the PA Global Stocktake [55], the CCAC-TR makes a creditworthy initial attempt at a Paris Test analysis of its carbon budgeting, but it requires improvement as key normative and quantitative parameters are not made sufficiently explicit to provide required clarity.

2.2 Defining policy relevant national scenarios consistent with the Paris goal

This section sets out the basis of four illustrative scenarios used here to examine the effect of different proportions of non-CO₂ and CO₂ mitigation within Ireland's carbon budgeting programme. The aim of this coarse-grained scenario assessment is to assess the aggregate temperature impact effect (represented by cumulative CO₂we from 2015) of alternative by-gas combinations defined by on four options for CH₄ mitigation by 2030. The proposed national programme sets out to limit total cumulative inventory emissions to 495 MtCO₂eq for the period 2021–2030 (comprising 295 MtCO₂eq for 2021–2025 and 200 MtCO₂eq for 2026–2030). Land use emissions under an illustrative CCAC-TR scenario are constrained to 37 MtCO₂eq (see Table 3-3 in [42] p. 42), but this will certainly be exceeded, so a total of 45 MtCO₂eq is allowed in this study for LUC emissions for this 2021–2030. This leaves a rounded cumulative total of 450 MtCO₂eq for all other sectors as a round figure scenario constraint for this period.

Up to June 2022, policy documents and political discussion in Ireland have focused on: a 10% reduction in CH₄ emissions by 2030 relative to 2018, as stated in the Food Vision 2030 agrifood policy [56]; and a 22–30% reduction in agricultural emissions by 2030 in the 2021 Climate Action Plan ([57] p. 10), though this rate range does not appear to apply to both CH₄ and N₂O equally as the announced measures appear to focus on N₂O. Given the proposed sectoral 2030 mitigation targets for the agricultural sector include reductions of 10%, 22% and 30% these targets are used here to define three scenarios that can inform policy. A fourth scenario, based on examination of what would be required to meet the GHG-QNZ level by 2050, targets a 43% reduction in CH₄ and N₂O by 2030. In each scenario from 2031 onwards, CH₄ emissions decrease at a rate of about 0.3% yr⁻¹, to stabilise its GWP* annual warming contribution thereafter, and N₂O emissions are also set to follow this same reduction rate from 2031. In Ireland, 93% of both CH₄ and N₂O are from agriculture therefore in this study non-CO₂ mitigation primarily requires corresponding agricultural policy to be aligned with achieving the non-CO₂ pathway.

An extended spreadsheet tool [58] previously developed for the analysis presented in [51] is used to define annual emissions pathways, excluding LUC, for 2015–2100 by-gas and in aggregate, using CO₂we via GWP*, but also showing both CO₂eq via GWP₁₀₀ for comparison. The tool sums cumulative emissions from the start of 2015, primarily to show the scenario warming impact by-gas and in aggregate using cumulative CO₂we. Recorded emissions are used for 2015–2020 or else, if not available, 2020 emissions echo 2019. Piecewise linear pathways are defined through chosen years – 2030, 2050 and 2100 – based on the by-gas percentage reductions achieved by each chosen year relative to 2020 emissions. The 2030 non-CO₂ target level is set first and the 2050 and 2100 CH₄ targets are set to ensure a stable CH₄ warming impact by 2050 given the 20-year lag-time inherent in GWP* partially reflecting the real lag time from CH₄ emission pulse to warming impact. For N₂O, the 2030, 2050 and 2100 targets echo those for CH₄. The net-CO₂ value is then adjusted to ensure 2021–2030 emissions total 450 MtCO₂eq.

Scenarios are named based on the initial "N" of Non-CO₂ and the initial "C" of net-CO₂ combined with the by-gas percentage reduction for each. The N values are 10%, 22%, 30% and 43%, and the C values are the corresponding CO₂ reduction by 2030 meeting the 450 MtCO₂eq cumulative target. For example, the N10.C76 scenario defines a 10% reduction in both of the

non-CO₂ gases, CH₄ and N₂O, by 2030 relative to 2020 and a corresponding 76% reduction in CO₂ emissions by 2030 to meet the target 10-year CO₂eq total.

As residual N₂O emissions due to fertilisation in agriculture will need to be balanced by CDR in the long-term, in each scenario the negative annual net-CO₂ level is adjusted to balance the N₂O emissions value in 2100. The final step in scenario definition is to adjust the 2050 net-CO₂ to a negative value sufficient to ensure that aggregate cumulative CO₂we returns to the GHG-QNZ level (after initial GHG-ONZ overshoot) by 2100 at latest. Note that, provided the average negative value for net-CO₂ is maintained over the duration of net negative values, the same total cumulative negative net-CO₂ value could be achieved in a scenario with a less negative 2050 net-CO₂ value (and hence a later peak cumulative net-CO₂ value).

2.3 Annual and cumulative charts: overshoot net zero versus quota net zero

Figure 1 provides a key to reading the 2015–2100 scenario results that are shown as stacked annual and corresponding cumulative emissions from 2015, with solid by-gas pathways shown separately for net-CO₂, N₂O, net-CO₂+N₂O (combining the warming effect of the long-lived climate pollutants), and CH₄. The primary focus is on the society-wide warming outcome over time, shown by the solid red line denoting aggregate [CO₂+N₂O+CH₄] GHGs in both charts compared to the horizontal dotted magenta line in the cumulative chart, denoting the national CO₂we quota (NCQ*) level estimated for the chosen Paris goal based on the central value of TCRE given in IPCC AR6-WGI. Dashed lines show CO₂eq pathways for CH₄ and for aggregate [CO₂+N₂O+CH₄]. The annual GWP₁₀₀ CH₄ line usefully shows the relative change in rate of annual CH₄ emissions by mass over time, but the cumulative CH₄ and aggregate dashed lines are only shown to illustrate the failure of GWP₁₀₀ to reflect the temperature impact of changes in CH₄ and aggregate GHGs including CH₄.




Figure 1. Annotation to assist reading Figure 2 scenario results. Showing stacked 2015–2100 annual and cumulative emissions charts, particularly to identify differing net zero definitions. N43.C56 is the scenario example shown here. Solid lines show $GWP*CO_2we$ and dashed lines show $GWP_{100}CO_2eq$.

The figure's annotations for aggregate [CO₂+N₂O+CH₄] GHGs emphasise the difference between the *overshoot net zero* (ONZ) at peak carbon debt and the later achievement of the stabilisation at *quota net zero* (QNZ) after a period of net negative CO₂we warming reduction sufficient to cancel the peak carbon debt (at the maximum overshoot when the ONZ is attained) to reach the QNZ by 2100 at latest. In the scenario shown in **Figure 1** (**N43.C56** in the results), the QNZ is reached by 2050 and sustained thereafter. Ideally, scenarios would not overshoot the QNZ level at all, but it is now too late for Ireland to avoid overshoot within this minimally equitable approach. Hence, scenarios for Ireland can aim to limit maximum overshoot, which occurs in the ONZ year and to return, thereafter, to the QNZ as soon as possible via sustained cuts in CH₄ yr⁻¹ and negative net-CO₂ within outlined limits.

3 Results:

3.1 Comparing illustrative policy-relevant Paris-consistent national scenarios

As per the scenario definition basis given in Section 2, **Figure 2** presents and compares results for the four illustrative 2015–2100 society-wide scenarios for Ireland – **N10.C76**, **N22.C69**, **N30.C64**, and **N43.C56** – defined on the basis of substantial 2020–2030 non-CO₂ reduction with non-CO₂ (N) cuts of 10–43% by 2030. As constructed, all four scenarios require extremely rapid reduction in annual net CO₂ emissions to CO₂-only net zero (CNZ) by 2040 at latest (for **N43.C56**), and lesser non-CO₂ reductions have an earlier CNZ. Net-CO₂ annual emissions remain negative after CNZ in all four scenarios, more deeply negative for lesser non-CO₂ reduction, and, by scenario definition, end in 2100 with annual negative CO₂ emissions balancing N₂O emissions from then onward.

In the annual emissions charts in **Figure 2**a, the 2020–2030 major reduction in the flow of non-CO₂ emissions, followed by a 0.3% yr⁻¹ decrease, is shown in the annual GWP₁₀₀ CO₂eq line charts, as a dashed blue line for CH₄, and a solid orange line for N₂O. Both CH₄ and N₂O gross annual emissions remain positive to 2100: relative to 2020, the 10–43% non-CO₂ cut by 2030, becomes a 17–47% reduction spread by 2050, and a 29–54% reduction spread by 2100. However, as seen by using GWP* CH₄ mitigation in the defining 2022–2030 period results in a lagged warming reduction that goes into negative annual CO₂we values for all scenarios, with more negative outcomes for deeper sustained reductions in annual CH₄, that also begin earlier. The initial rise in CH₄ CO₂we from 2015 reflects prior increases in CH₄ emissions over the previous decade due to expansion of ruminant agriculture, and this rise in CO₂we is only reversed after reflecting the delayed warming response to CH₄ flow changes that is at least partially incorporated in GWP* usage. After ONZ, the lagged CH₄ warming reduction effect of 2020–2030 CH₄ mitigation shown as negative annual CO₂we values continues until 2050, after which CH₄ CO₂we emissions are zero due to the 0.3% yr⁻¹ decline in CH₄ CO₂eq, directly reflecting the change in CH₄ mass emissions.

In **Figure 2**b, stacked below and aligned with the annual emission charts, are corresponding line charts for 2015–2100 cumulative CO₂we emissions, by-gas and in aggregate, reflecting their warming contribution in the scenarios. (The dashed cumulative GWP₁₀₀ CO₂eq lines for CH₄ and aggregate are presented only to show that they do not reflect warming outcomes

2nd International Conference on Negative CO₂ Emissions, June 14-17, 2022, Göteborg, Sweden

involving CH_4 mitigation). Zero for cumulative emissions is set at the beginning of 2015 – the "minimally




Figure 2. Results for four illustrative 2015–2100 scenarios for Ireland consistent with 1.5°C 50%. Scenarios reach a national CO_2 we quota for $CO_2+N_2O+CH_4$ by 2100 at latest. CH_4 annual emissions mitigation relative to 2020 increases from left to right: 10%, 22%, 30%, and 43%. The horizontal dotted line in the cumulative charts shows the 1.5°C 50% NCQ* quota target level. All emissions values in Mt with vertical axes matched to enable direct comparison. For all scenarios: the total GWP_{100} cumulative budget for 2021-2030 is 450 MtCO2eq; in 2100 annual CDR equal to annual N_2O ; and 2050 net CO_2 adjusted to ensure net zero at quota level is reached by 2100 at latest. Only N43.C56 reaches QNZ by 2050. (a) Annual emission pathways: solid lines for net CO_2 (black), N_2O in CO_2 eq (orange), CH_4 in CO_2 we (blue), and aggregate CO_2 eq (red). (b) Cumulative emissions from 2015 corresponding to the annual emissions pathways, including long-lived climate pollutants summing CO_2+N_2O (purple solid line). Below (b) are bar charts of cumulative CO_2 we by-gas and in aggregate, including pale bars at right for each scenario

Below (b) are bar charts of cumulative CO_2 we by-gas and in aggregate, including pale bars at right for each scenario showing aggregate CO_2 eq (pink) and CH_4 (pale blue), for: (c) 2021–2030; (d) 2021–2050; and (e) 2021–2100.

equitable" baseline year for this study while acknowledging the serious equity concerns previously discussed. All scenarios are consistent with aligning with a long-term goal of a 50% chance of limiting to 1.5°C by stabilising, by 2100 at latest, with the estimated population-based national QNZ level of cumulative 410 MtCO₂we from 2015 for CO₂+N₂O+CH₄. This level is shown as a horizontal dotted line that is reached by aggregate emissions by 2050 in **N43.C56** and only by 2100 in the other three scenarios. All four scenarios go into overshoot of this QNZ level by 2023, after which *carbon debt* accumulates up to a peak at maximum overshoot

corresponding to ONZ ("no further warming") in the annual charts. Peak carbon debt is highest for N10.C76 and overshoot is most strongly limited by the warming reduction effect of increased CH₄ mitigation up to N43.C56.

The depth of CH₄ mitigation is also seen to be critical in determining the cumulative amount of net negative net-CO₂ required to cancel the carbon debt completely to return to an annual QNZ Paris Test quota level. In **N43.C56** the CH₄ mitigation is sufficient to entirely cancel the overshoot carbon debt by 2050 and net-CDR is only needed to balance N₂O emissions. By contrast the other three scenarios require additional net-CDR to compensate for shallower mitigation in annual CH₄ emissions rate in cancelling a larger carbon debt as well as balancing somewhat higher N₂O emissions. For **N43.C56**, CDR (net negative net-CO₂) is required at an average sequestration rate of -2.6 MtCO₂ yr⁻¹ over 67 years, whereas **N10.C76** requires an average of -10 MtCO₂ yr⁻¹ over 60 years.

The bottom of Figure 2, shows bar charts of cumulative CO2we by-gas and for aggregate GHGs over (c) 2021-2030 (d) 2021-2050 and (e) 2021-2100, respectively, including pale bars at right for each scenario showing cumulative CO2eq for aggregate GHGs (pink) and CH4 (pale blue). The CO2we values reveal the substantially smaller warming impact from CH4 and the dependent aggregate GHG than is indicated by GWP_{100} .

For the four illustrative scenarios, **Table 1** sets out the ONZ year of maximum target overshoot, with the peak carbon debt in MtCO₂we reached at that time, the timing of CO₂ net zero (CNZ); and the year when the QNZ is reached by cumulative aggregate CO₂we for CO₂+N₂O+CH₄. Only the **N43.C56** scenario reaches the QNZ by 2050, the other three meet it in 2100. As shown in **Table 1**, with increasing depth of non-CO₂ mitigation, from N10.C76 through to **N43.C56** the scenarios show reduced maximum carbon debt relative to the QNZ cumulative threshold, while the ONZ year occurs sooner and the CNZ year later.

Table 1. Timing of scenario net zero years and with maximum overshoot carbon in MtCO₂we.

Net zero timing and C-debt by Scenario	N10.C76	N22.C69	N20.C64	N43.C56
Overshoot Net Zero (ONZ) occurs in	2040	2037	2036	2033
Max carbon debt at ONZ (MtCO2we)	322	249	206	146
Net-CO ₂ Net Zero (CNZ) occurs in	2038	2041	2043	2047
Quota Net Zero (QNZ) occurs in	2100	2100	2100	2050

Figure 3 presents stacked bar comparison of the scenario cumulative net-CO₂we values by-gas for 2021–2050 and 2021–2100, with cumulative positive net-CO₂ values up to ONZ (grey bars) presented separately from cumulative negative net-CO₂ (net CDR) values after ONZ. In **Figure 3**a, the maximum cumulative net CDR is -105 MtCO₂we because, even with radical and extreme CO₂ mitigation it takes time for net CO₂ to reduce to CNZ. In contrast, CH₄ mitigation, primarily through reduction in ruminant agriculture, achieves -394 MtCO₂we by 2050. **Figure 3**b shows the required amounts of net-CO₂we needed for each scenario. For all scenarios the total 2021–2100 cumulative CO₂we for the sum of net-CDR and CH₄ is ~560 MtCO₂we revealing the important warming impact trade-off between CH₄ mitigation and net-CDR requirement. Shallower CH₄ reduction results in a requirement for greater net CDR due to

substantially greater overshoot, increasing the peak carbon debt at ONZ, and somewhat higher cumulative N_2O emissions due to the scenario definition of identical by-mass mitigation rates for CH_4 and N_2O .

Given a practical maximum CDR of cumulative -200 MtCO₂ by 2100, as assessed in [59], only **N43.C56**, the scenario with the largest non-CO₂ reduction, achieves a net-CDR level lower than this threshold at -172 MtCO₂. Minimising CDR to within the practical limit is primarily enabled by of the large methane mitigation warming reduction of -394 MtCO₂we. The N10.C76 scenario requires -604 MtCO₂, far greater than the practical CDR threshold; the **N22.C69** and **N30.C64** scenarios also fail to meet this threshold.




Figure 3. Scenario by-gas CO_2 -we values for (a) 2021–2050 and (b) 2021–2100. The level dotted line at 118 $MtCO_2$ we indicates the CO_2 we national quota of CO_2 + N_2O + CH_4 remaining from 2021 onward, based on depletion of the 2015 remaining quota over 2015–2021. In (b), the level, light blue dashed line indicates the net warming reduction due to the sum of CH_4 emission rate change and net-CDR.




Figure 4. Scenario carbon debt and net negative emissions. (a) Carbon debt at overshoot net zero (ONZ) and in 2050, (b) Cumulative negative net-CO₂ (CDR requirement) up to 2100.

Notably, although the annual CO₂eq flow of both N₂O and CH₄ are reduced by the same rate in each scenario, primarily up to 2030 at each scenario's given non-CO₂ rate, and only very slowly thereafter, the scenarios' temperature impact range for N₂O is 420 to 277 MtCO₂we, a spread of 143 MtCO₂we, yet the range for CH₄ is +40 to -394 MtCO₂we, a spread of 430 MtCO₂we. This illustrates the large CH₄ TIR opportunity available that can significantly limit near-term warming in addition to mitigating CO₂ and N₂O. Importantly, in agricultural mitigation assessment relative to a temperature goal, CH₄ and N₂O are not simply exchangeable on a CO₂eq basis. Therefore, CH₄ mitigation is a priority in effective climate action if substantial

overshoot or breaching of potential CDR limits is possible. In the scenarios, as shown in **Figure** 4a the national overshoot carbon debt can by substantial at ONZ and in 2050, and, as in **Figure** 4b, only the **N43.C56** scenario constrains the CDR requirement within Ireland's assessed practical limit of 200 MtCO₂ to 2100 suggested in [59]. Substituting CO₂ or N₂O for apparently equivalent CO₂eq reductions in CH₄ via GWP₁₀₀ will result in greater scenario warming, as the cumulative CO₂we outcomes reveal via use of GWP*.

4 Discussion

4.1 CH₄ mitigation in limiting overshoot and CDR reliance

The stark reality of what is now necessary for good faith PA-aligned mitigation by a highemitting developed Party is plainly conveyed by all four indicative national scenarios in this coarse-grained modelling. Under equal per capita sharing of the defined global warming budget (rGCB*), Ireland's aggregate carbon quota (NCQ*) for CO₂+N₂O+CH₄ was 410 MtCO₂we in 2015, but as of the start of 2021 less than 120 MtCO₂we remained after quota depletion by 2015–2020 emissions. Furthermore, this does not allow for further reductions in the basis for the quota that need acknowledgment, including the issue that IAM's overestimate 1.5°C global carbon budgets by about 20% [60], or that the national share of global warming due to international aviation and shipping [30] is not accounted for, even though Ireland's frequentflying citizens and its airlines could be deemed inequitably responsible [61], [62]. Even without these considerations, overshoot of Ireland's 2015-basis NCQ* quota is imminent, occurring in 2023 in all four scenarios. On this basis, radical reductions in all GHGs are urgently required, especially CO₂ and CH₄, starting immediately, at rates well beyond what is generally considered feasible in the national energy and agricultural economics-based modelling of society-wide transition that have hitherto informed climate advisory reporting and emissions projections [63]. If deep reductions in agricultural GHGs are not achieved energy decarbonisation costs are 'extraordinarily challenging' in recent notionally "least cost" energy modelling [64]. Any further delay in meeting the very deep mitigation now required to align national climate action with 'pursuing efforts to limit the temperature increase to 1.5°C above pre-industrial levels will only increase overshoot peak carbon debt at ONZ and the amount of net warming reduction then required to return to the quota level QNZ via some combination of net CDR and CH₄ reduction. As shown in the scenario results, only deep and early cuts in annual CH₄ emissions, implying substantial mandated reductions in ruminant agriculture, can achieve sufficient warming reduction to effectively limit overshoot by the 2050 date noted in the climate action plans of many Parties and limit CDR within an assessed practical storage limit. Instead, by taking advantage of the ending of the EU milk quota, Ireland's 60% expansion in milk intake from 2010 to 2020 (an outlier in the EU) and a coupled rise in CH₄ emissions, has been driven by agri-food industry strategy endorsed by governments as policy [65], despite the evident conflict with declared climate and environmental policy [66].

For all Parties, substantially reducing the annual CH₄ emissions rate can effectively be considered a negative emission technology, equivalent to net CDR by achieving a warming reduction equivalent to a one-off removal of CO₂ as estimated by CO₂we via use of the GWP* method. Methane emission factors for agriculture and energy are established in UNFCCC

inventory reporting and are directly related to activity levels of animal farming, fossil fuel combustion and waste handling. By contrast, CDR technology at the scale needed to achieve PA-aligned mitigation at global or high-emitting Party *without* the CH₄ mitigation seen in IPCC global scenarios, or national-level scenarios as presented here, does not yet exist at the scale required, and must be deemed highly uncertain thereby incurring higher cost and moral hazard given the risk of non-achievement.

4.2 Implications for Ireland's carbon budgeting and sectoral ceilings.

Relative to other UNFCCC Parties, Ireland, like New Zealand, has high CH₄ emissions due to ruminant agriculture, so these nations have a particularly large agricultural CH₄ mitigation opportunity in limiting overshoot and returning to QNZ at the NCQ* level. Achieving the Parisconsistent N43.C56 scenario would require immediate policy action to limit agricultural milk and livestock (meat) production. This is politically difficult, but without deep CH₄ reduction, as well as reducing fossil fuel combustion for power, industry, buildings and transport (with high costings in recent least cost energy modelling), it is rapidly becoming impossible to meet the long-term goal. Ireland's CCAC in 2021 operating under time pressure to provide for 2021— 2030 carbon budgets under the amended climate Act, presented five alternative "core scenarios" in its CCAC-TR [42] confirming that cutting CH₄ has the largest warming impact compared to cutting CO₂ and N₂O. Contrary to our results, though similarly based on an 1.5°C rGCB* equal per capita sharing approach, the advisory report appears to overestimate the rGCB*, indicates that no core scenario overshoot of warming quota would occur, and suggests that a 19% reduction in non-CO₂ by 2030 could achieve a "Paris Test" quota threshold by 2050. However, the report appears to overestimate the rGCB* for their core scenario basis of [CO₂+N₂O+CH₄] uses a GWP* time averaging parameter Δt of 1 year rather than the 20 years advised in GWP* literature [37], and the IPCC AR6 2020 reference as a base year, which is arguably less than minimally equitable for fair share assessment [43]. Our scenario results, also in the context of equal per capita sharing of a 1.5°C 50% rGCB*, but assessed on the basis of a literature-justified base year of 2015 and standard GWP* analysis using literature-recommended parameters, indicate that the CCAC-TR requires reassessment. Toward future improvement of the CCAC's Paris Test, a separate paper in preparation will address these scientific and normative issues.

The results show that overshoot of Ireland's NCQ* limit is imminent and only scenarios with the deepest CH₄ reduction of more than 40% by 2030 can limit overshoot carbon debt and reduce tacit reliance on substantial and highly uncertain net-CDR achievement in excess of balancing ongoing N₂O and within the 200 MtCO₂ CDR limit. The 10% CH4 reduction in the Food Vision 2030 policy [56], and the range of 22–30% in agricultural non-CO₂ CO₂eq emissions by 2030 reduction put forward in Ireland's 2021 Climate Action Plan [57], fall well short of the scenario 43% reduction in annual CH₄ emissions found in our modelling as required to achieve effective society-wide mitigation to meet a 2050 quota target, while limiting overshoot and restricting reliance on CDR to repay carbon debt. Concerningly, the proposed agricultural mitigation options in the Climate Action Plan emphases N₂O reduction to achieve the CO₂eq reduction; and the asserted "with additional measures" CH₄ mitigation by 2030 does not appear to be physically achievable, especially given policy that continues to support growth in ruminant-based agricultural production. The possibility of Paris-consistent climate action in Ireland is rapidly being lost due to such policy incoherence.

4.3 Implications for high emitting Parties

The coarse-grained scenario analysis presented for Ireland is indicative for many high emitting Parties: aligning equitable action with the PA-goal requires radical reductions in fossil fuel use, far faster than is generally being considered in advisory documents and research, and effective regulatory efforts to directly abate so-called "hard-to-abate" sectors are also now required. For such Parties, even radical net-CO2 reduction will not be enough to avoid near-term overshoot of fair share GHG quotas CH₄ mitigation to limit overshoot and reliance on CDR to cut carbon debt. A preliminary analysis for the EU, on the same 1.5°C scenario basis as here for Ireland, indicates a later 2032 overshoot ONZ year, but similarly the aggregate pathway relies on CH₄ reduction to limit carbon debt and achieve an earlier return to QNZ at the quota level to limit CDR reliance. In further research, more accurate Paris Test analysis for the EU or other Parties needs all climate action policy to show the by-gas scenario emission pathways for all key GHGs from all sectors under proposed scenario alternatives. Although Ireland's governance system continues to struggle to achieve meaningful climate action, assessing the level of committed action has been greatly assisted by the legal requirements under Ireland's amended Climate Act for near-term carbon budgeting, with cumulative limits on the 2021–2030 CO₂eq totals, legally binding subordinate sectoral budgets, and a need to show that these near-term budgets are consistent with meeting the Paris Agreement goal equitably. Other Parties could benefit from examining Ireland's carbon budgeting outline and progress. As shown in this study, the use of GWP* methodology enables comparative assessment of the warming impact of aggregate scenario emissions including CH₄ through calculation of cumulative CO₂we and production of alternative scenarios achieving a fair share of the remaining global GHG warming budget (cumulative CO₂we) from a global common base year.

As the now-abandoned EU milk quota showed, it is possible to apply supply-side limits on nutrient input and animal agriculture output that limit or cut CH₄ emissions from enteric fermentation and GHGs from animal excretion, while still providing the same or greater food production [21]-[24]; and that removing this restriction can result in emissions and warming impact increasing rapidly as has occurred in Ireland [25]. Compared to plant-based diets, food production by animal agriculture is relatively nutrient and land inefficient [26], [27], [22] and reductions in ruminant production and derived food consumption, in particularly in developed Parties, would contribute to meeting the Paris goal through methane mitigation, with environmental and social co-benefits [28], [29]. Similarly, beyond the uncertain effect of proposed technical measures, future aviation and shipping emissions [30] could be directly limited by policy and regulatory instruments to reduce frequent flying [31] or to cut consumption of shipped products through demand management [32]. It should also be noted that the tertiary or 'service' sector cannot be considered as inherently low carbon [33]. Therefore, it is highly questionable to categorise agriculture and LUC, or aviation and shipping, or finance and services, in ways that exclude or partially exclude them from global or Party carbon budgeting in relevant advice to decisionmakers. Assessment needs to show the different temperature impacts of different by-gas and aggregate GHG pathways for scenario options across all sectors relative to a quantified and normative Paris temperature goal definition in a CBDR-RC context. The coarse-grained modelling presented here enables such a Party-level assessment.

4.4 Asserting CDR reliance for so-called "hard-to-abate" sectors is hard to justify AR6-WGIII Ch. 12.3 states:

Within ambitious mitigation strategies at global or national levels, CDR cannot serve as a substitute for deep emissions reductions but can fulfil multiple complementary roles: (1) further reduce net CO₂ or GHG emission [67] levels in the near-term; (2) counterbalance residual emissions from 'hard-to-transition' sectors, such as CO₂ from industrial activities and long-distance transport (e.g., aviation, shipping), or methane and nitrous oxide from agriculture, in order to help reach net zero CO₂ or GHG emissions in the mid-term; (3) achieve and sustain net-negative CO₂ or GHG emissions in the long-term, by deploying CDR at levels exceeding annual residual gross CO₂ or GHG emissions

As this article's results show at a Party level, this characterisation is potentially misleading because GWP₁₀₀ does not reflect the limiting of aggregate temperature impact by rapid CH₄ mitigation. Instead as is noted in AR6-WGIII Ch. 2, using simple climate models, or new approaches like GWP* or CGTP that approximate such models, can show temperature impact of multi-gas mitigation scenarios. The quoted characterisation above reflects a common but problematic presentation common in CDR literature and reviews [68]–[73], including Ch. 12 and other AR6-WGIII chapters (apart from Ch. 2 and 3), whereby GHG analyses based on the GWP₁₀₀ CO₂eq equivalence metric are used to categorise the GHG emissions of particular sectors as "hard-to-abate", thereby potentially misleadingly suggesting that CDR can substantively offset these sector emissions in the near-term and their residual emissions entirely in the long-term. Such CDR-focused reviews fail to make it sufficiently clear that substantial and sustained immediate reductions in CH₄ from all sources, including agriculture, would result in a significant and more certain near-term TIR than from CDR. Mitigation deterrence through appeals to technical fixes is an ongoing issue in climate policy as described by [67]. In short, it does not make sense to "counterbalance" any ongoing CH₄ emissions on a GWP₁₀₀ basis with CDR, as doing so is too liable to cause decisionmakers to overlook the greater near-term TIR effectiveness and certainty of CH₄ mitigation and thereby deter near-term CH₄ mitigation effort. As in our methodology, Paris consistency for a Party can be examined by evaluating the aggregate temperature impact over time of alternative society-wide options relative to meeting a quota net zero (QNZ) level corresponding to an estimated fair share temperature impact from a common base year based on defined normative and quantitative basis. A Party achieving "no further warming" ONZ while in overshoot of a minimally equitable PA carbon budget cannot be said to be consistent with PA Article 2.

5 Conclusion

For developing or poorer nations with low per capita emissions, reducing their livestock and other CH₄ emissions is not important within the fair sharing GHG budget framework presented here because they are likely not at risk of near-term GHG quota overshoot, even with substantial increases in near-term fossil fuel use. However, for developed nations with high ongoing emissions, overshoot is already imminent in this fair share context. Therefore, *in addition to*

radical CO₂ emissions reduction, substantial CH₄ mitigation can limit peak carbon debt at overshoot net zero (ONZ) and hasten cancelation of this debt to return to quota net zero (QNZ) within a mitigation timeframe centred on 2050. Any policy reliance on CDR to balance a very limited level of long-term residual emissions will need to be assessed with care on the basis of equity as '[a]ny further delay in concerted anticipatory global action on adaptation and mitigation will miss a brief and rapidly closing window of opportunity to secure a liveable and sustainable future for all.' [7]. Consequently, the simplistic assertion in much CDR literature that whole sectors, notably intensive ruminant agriculture, are "hard-to-abate is hard to justify in the CBDR-RC context required by the Paris Agreement and too readily enables mitigation deterrence among developed Party decisionmakers and regulation of such sectors. As our results demonstrate, urgent fossil and agricultural CH₄ emissions mitigation over the next decade to enable temperature impact reduction is important to reduce reliance on costly and uncertain CDR, so it deserves much greater focus in national mitigation policy assessments. The coarse-grained methodology presented is easily applicable to any nation or regional UNFCCC Party, enabling rapid comparison of society-wide, aggregate pathway, carbon budget options to align Party-level action with meeting the PA temperature goal equitably.

6 References

- [1] UNFCCC, 'Paris Agreement'. 2015. [Online]. Available: https://unfccc.int/files/essential_background/convention/application/pdf/english_paris_agreement.pdf
- [2] L. Rajamani and J. Werksman, 'The legal character and operational relevance of the Paris Agreement's temperature goal', Philos. Trans. R. Soc. Math. Phys. Eng. Sci., vol. 376, no. 2119, p. 20160458, May 2018, doi: 10.1098/rsta.2016.0458.
- [3] L. Rajamani et al., 'National "fair shares" in reducing greenhouse gas emissions within the principled framework of international environmental law', Clim. Policy, vol. 21, no. 8, pp. 983–1004, Sep. 2021, doi: 10.1080/14693062.2021.1970504.
- [4] K. Dooley et al., 'Ethical choices behind quantifications of fair contributions under the Paris Agreement', Nat. Clim. Change, vol. 11, no. 4, pp. 300–305, Apr. 2021, doi: 10.1038/s41558-021-01015-8.
- [5] M. Meinshausen et al., 'Realization of Paris Agreement pledges may limit warming just below 2 °C', Nature, vol. 604, no. 7905, Art. no. 7905, Apr. 2022, doi: 10.1038/s41586-022-04553-z.
- [6] IPCC-WGI, 'AR6 WGI Summary for Policymakers', 2021. Accessed: Aug. 11, 2021. [Online]. Available: https://www.ipcc.ch/report/ar6/wg1/downloads/report/IPCC AR6 WGI SPM.pdf
- [7] IPCC WGII, 'AR6 WGII Summary For Policymakers', Intergovernmental Panel on Climate Change, Feb. 2022. Accessed: Feb. 28, 2022. [Online]. Available: https://report.ipcc.ch/ar6wg2/pdf/IPCC_AR6_WGII_SummaryForPolicymakers.pdf
- [8] IPCC AR6 WGIII, 'AR6 WGIII Summary For Policymakers', 2022. Accessed: Apr. 04, 2022. [Online]. Available: https://report.ipcc.ch/ar6wg3/pdf/IPCC AR6 WGIII SummaryForPolicymakers.pdf
- [9] D. H. Matthews et al., 'An integrated approach to quantifying uncertainties in the remaining carbon budget', Commun. Earth Environ., vol. 2, no. 1, pp. 1–11, Jan. 2021, doi: 10.1038/s43247-020-00064-9.

- [10] Y. Ou et al., 'Deep mitigation of CO2 and non-CO2 greenhouse gases toward 1.5 °C and 2 °C futures', Nat. Commun., vol. 12, no. 1, p. 6245, Oct. 2021, doi: 10.1038/s41467-021-26509-z.
- [11] M. R. Allen, J. S. Fuglestvedt, K. P. Shine, A. Reisinger, R. T. Pierrehumbert, and P. M. Forster, 'New use of global warming potentials to compare cumulative and short-lived climate pollutants', Nat. Clim. Change, vol. 6, no. 8, pp. 773–776, May 2016, doi: 10.1038/nclimate2998.
- [12] W. J. Collins et al., 'Increased importance of methane reduction for a 1.5 degree target', Environ. Res. Lett., vol. 13, no. 5, p. 054003, Apr. 2018, doi: 10.1088/1748-9326/aab89c.
- [13] D. P. van Vuuren et al., 'Alternative pathways to the 1.5 °C target reduce the need for negative emission technologies', Nat. Clim. Change, Apr. 2018, doi: 10.1038/s41558-018-0119-8.
- [14] N. Mengis and H. D. Matthews, 'Non-CO2 forcing changes will likely decrease the remaining carbon budget for 1.5 °C', Npj Clim. Atmospheric Sci., vol. 3, no. 1, p. 19, Dec. 2020, doi: 10.1038/s41612-020-0123-3.
- [15] N. Grant, A. Hawkes, S. Mittal, and A. Gambhir, 'Confronting mitigation deterrence in low-carbon scenarios', Environ. Res. Lett., vol. 16, no. 6, p. 064099, Jun. 2021, doi: 10.1088/1748-9326/ac0749.
- [16] D. McLaren, 'Quantifying the potential scale of mitigation deterrence from greenhouse gas removal techniques', Clim. Change, vol. 162, no. 4, pp. 2411–2428, Oct. 2020, doi: 10.1007/s10584-020-02732-3.
- [17] L. Rajamani, 'AMBITION AND DIFFERENTIATION IN THE 2015 PARIS AGREEMENT: INTERPRETATIVE POSSIBILITIES AND UNDERLYING POLITICS', Int. Amp Comp. Law Q., vol. 65, no. 2, pp. 493–514, Apr. 2016, doi: 10.1017/S0020589316000130.
- [18] A. Shibata, 'Part III Conceptual Pillars, Ch.22 Good Faith', Oxford Public International Law, 2021. https://opil.ouplaw.com/view/10.1093/law/9780198849155.001.0001/law-9780198849155-chapter-22 (accessed Apr. 27, 2022).
- [19] J. Allwood et al., 'Absolute Zero', Apollo University of Cambridge Repository, Nov. 2019. doi: 10.17863/CAM.46075.
- [20] IPCC, 'IPCC AR6 WGIII Final Draft Full Report', Intergovernmental Panel on Climate Change, 2022. Accessed: Apr. 04, 2022. [Online]. Available: https://report.ipcc.ch/ar6wg3/pdf/IPCC AR6 WGIII FinalDraft FullReport.pdf
- [21] E. Stehfest, L. Bouwman, D. P. van Vuuren, M. G. J. den Elzen, B. Eickhout, and P. Kabat, 'Climate benefits of changing diet', Clim. Change, vol. 95, no. 1, pp. 83–102, Jul. 2009, doi: 10.1007/s10584-008-9534-6.
- [22] E. S. Cassidy, P. C. West, J. S. Gerber, and J. A. Foley, 'Redefining agricultural yields: from tonnes to people nourished per hectare', Environ. Res. Lett., vol. 8, no. 3, p. 034015, Sep. 2013, doi: 10.1088/1748-9326/8/3/034015.
- [23] G. Billen, L. Lassaletta, and J. Garnier, 'A vast range of opportunities for feeding the world in 2050: trade-off between diet, N contamination and international trade', Environ. Res. Lett., vol. 10, no. 2, p. 025001, Jan. 2015, doi: 10.1088/1748-9326/10/2/025001.
- [24] Z. Sun et al., 'Dietary change in high-income nations alone can lead to substantial double climate dividend', Nat. Food, vol. 3, no. 1, pp. 29–37, Jan. 2022, doi: 10.1038/s43016-021-00431-5.
- [25] P. R. Price and B. McMullin, 'Assessing methane (CH4) from Irish agriculture in climate policy 2005–2020 using the GWP₁₀₀ and GWP* greenhouse gas (GHG) equivalence metrics', Dublin City University, Working Paper, 2020. [Online]. Available: https://tinyurl.com/IE-Agri-CH4-GWPstar-GWP₁₀₀

- [26] M. N. Hayek, H. Harwatt, W. J. Ripple, and N. D. Mueller, 'The carbon opportunity cost of animal-sourced food production on land', Nat. Sustain., vol. 4, no. 1, pp. 21–24, Jan. 2021, doi: 10.1038/s41893-020-00603-4.
- [27] J. A. Foley et al., 'Solutions for a cultivated planet', Nature, vol. 478, no. 7369, pp. 337–342, Oct. 2011, doi: 10.1038/nature10452.
- [28] W. J. Ripple, P. Smith, H. Haberl, S. A. Montzka, C. McAlpine, and D. H. Boucher, 'Ruminants, climate change and climate policy', Nat. Clim. Change, vol. 4, no. 1, pp. 2–5, Jan. 2014, doi: 10.1038/nclimate2081.
- [29] M. A. Clark et al., 'Global food system emissions could preclude achieving the 1.5° and 2°C climate change targets', Science, vol. 370, no. 6517, pp. 705–708, Nov. 2020, doi: 10.1126/science.aba7357.
- [30] K. Esmeijer, M. den Elzen, and H. van Soest, 'Analysing international shipping and aviation emission projections', PBL Netherlands Environmental Assessment Agency, 4076, 2020. [Online]. Available: https://www.pbl.nl/sites/default/files/downloads/pbl-2020-analysing-international-shipping-and-aviation-emissions-projections_4076.pdf
- [31] S. Gössling and A. Humpe, 'The global scale, distribution and growth of aviation: Implications for climate change', Glob. Environ. Change, vol. 65, p. 102194, Nov. 2020, doi: 10.1016/j.gloenvcha.2020.102194.
- [32] A. Bows-Larkin, 'All adrift: aviation, shipping, and climate change policy', Clim. Policy, vol. 15, no. 6, pp. 681–702, Nov. 2015, doi: 10.1080/14693062.2014.965125.
- [33] D. Horen Greenford, T. Crownshaw, C. Lesk, K. Stadler, and H. D. Matthews, 'Shifting economic activity to services has limited potential to reduce global environmental impacts due to the household consumption of labour', Environ. Res. Lett., vol. 15, no. 6, p. 064019, Jun. 2020, doi: 10.1088/1748-9326/ab7f63.
- [34] K. Anderson and G. Peters, 'The trouble with negative emissions', Science, vol. 354, no. 6309, pp. 182–183, Oct. 2016, doi: 10.1126/science.aah4567.
- [35] A. Larkin, J. Kuriakose, M. Sharmina, and K. Anderson, 'What if negative emission technologies fail at scale? Implications of the Paris Agreement for big emitting nations', Clim. Policy, Aug. 2017, [Online]. Available: http://www.tandfonline.com/doi/abs/10.1080/14693062.2017.1346498
- [36] M. Cain, J. Lynch, M. R. Allen, J. S. Fuglestvedt, D. J. Frame, and A. H. Macey, 'Improved calculation of warming-equivalent emissions for short-lived climate pollutants', NPJ Clim. Atmospheric Sci., vol. 2, no. 1, pp. 1–7, Sep. 2019, doi: 10.1038/s41612-019-0086-4.
- [37] J. Lynch, M. Cain, R. Pierrehumbert, and M. Allen, 'Demonstrating GWP*: a means of reporting warming-equivalent emissions that captures the contrasting impacts of short-and long-lived climate pollutants', Environ. Res. Lett., vol. 15, no. 4, p. 044023, Apr. 2020, doi: 10.1088/1748-9326/ab6d7e.
- [38] M. A. Smith, M. Cain, and M. R. Allen, 'Further improvement of warming-equivalent emissions calculation', Npj Clim. Atmospheric Sci., vol. 4, no. 1, Art. no. 1, Mar. 2021, doi: 10.1038/s41612-021-00169-8.
- [39] W. J. (Bill) Collins, D. J. Frame, J. Fuglestvedt, and K. P. Shine, 'Stable climate metrics for emissions of short and long-lived species combining steps and pulses', Environ. Res. Lett., 2020, doi: 10.1088/1748-9326/ab6039.
- [40] M. Meinshausen and Z. Nicholls, 'GWP* is a model, not a metric', Environ. Res. Lett., Feb. 2022, doi: 10.1088/1748-9326/ac5930.
- [41] J. Rogelj and C.-F. Schleussner, 'Unintentional unfairness when applying new greenhouse gas emissions metrics at country level', Environ. Res. Lett., Sep. 2019, doi: 10.1088/1748-9326/ab4928.
- [42] CCAC, 'Carbon Budget Technical Report October 2021', Climate Change Advisory Council, Oct. 2021. Accessed: Oct. 25, 2021. [Online]. Available:

- https://www.climatecouncil.ie/media/climatechangeadvisorycouncil/Technical%20report%20on%20carbon%20budgets%2025.10.2021.pdf
- [43] B. McMullin, P. Price, M. B. Jones, and A. H. McGeever, 'Assessing negative carbon dioxide emissions from the perspective of a national "fair share" of the remaining global carbon budget', Mitig. Adapt. Strateg. Glob. Change, Jul. 2019, doi: 10.1007/s11027-019-09881-6.
- [44] A. Larkin, J. Kuriakose, M. Sharmina, and K. Anderson, 'What if negative emission technologies fail at scale? Implications of the Paris Agreement for big emitting nations', Clim. Policy, vol. 18, no. 6, pp. 690–714, Aug. 2017, doi: 10.1080/14693062.2017.1346498.
- [45] P. Smith, 'Soil carbon sequestration and biochar as negative emission technologies', Glob. Change Biol., vol. 22, no. 3, pp. 1315–1324, Mar. 2016, doi: 10.1111/gcb.13178.
- [46] B. Mackey et al., 'Untangling the confusion around land carbon science and climate change mitigation policy', Nat. Clim. Change, vol. 3, no. 6, pp. 552–557, May 2013, doi: 10.1038/nclimate1804.
- [47] H. Herzog, K. Caldeira, and J. Reilly, 'An Issue of Permanence: Assessing the Effectiveness of Temporary Carbon Storage', Clim. Change, vol. 59, no. 3, pp. 293–310, Aug. 2003, doi: 10.1023/A:1024801618900.
- [48] M.-K. Kim, B. A. McCarl, and B. C. Murray, 'Permanence discounting for land-based carbon sequestration', Ecol. Econ., vol. 64, no. 4, pp. 763–769, Feb. 2008, doi: 10.1016/j.ecolecon.2007.04.013.
- [49] P. Smith, 'Do grasslands act as a perpetual sink for carbon?', Glob. Change Biol., vol. 20, no. 9, pp. 2708–2711, 2014, doi: 10.1111/gcb.12561.
- [50] J. Fuglestvedt et al., 'Implications of possible interpretations of "greenhouse gas balance" in the Paris Agreement', Philos. Trans. R. Soc. Math. Phys. Eng. Sci., vol. 376, no. 2119, p. 20160445, May 2018, doi: 10.1098/rsta.2016.0445.
- [51] B. McMullin and P. Price, 'Synthesis of Literature and Preliminary Modelling Relevant to Society-wide Scenarios for Effective Climate Change Mitigation in Ireland 2016-CCRP-MS.36', Environmental Protection Agency, EPA Research Report 352, 2020. [Online]. Available: https://www.epa.ie/publications/research/climate-change/Research Report 352.pdf
- [52] B. McMullin and P. Price, 'TECHNICAL REPORT Society-wide Scenarios for Effective Climate Change Mitigation in Ireland (Grant number 2018-CCRP-DS.14)', Dublin City University, EPA Research Report, Nov. 2020. Accessed: Nov. 06, 2020. [Online]. Available: http://doras.dcu.ie/25144/1/SSECCM-TR-2018-CCRP-DS.14 Final%20Technical%20Report.pdf
- [53] S. Kartha et al., 'Cascading biases against poorer countries', Nat. Clim. Change, vol. 8, no. 5, pp. 348–349, May 2018, doi: 10.1038/s41558-018-0152-7.
- [54] H. Winkler, N. Höhne, G. Cunliffe, T. Kuramochi, A. April, and M. J. de Villafranca Casas, 'Countries start to explain how their climate contributions are fair: more rigour needed', Int. Environ. Agreem. Polit. Law Econ., vol. 18, no. 1, pp. 99–115, Feb. 2018, doi: 10.1007/s10784-017-9381-x.
- [55] H. Winkler, 'Putting equity into practice in the global stocktake under the Paris Agreement', Clim. Policy, vol. 20, no. 1, pp. 124–132, Jan. 2020, doi: 10.1080/14693062.2019.1680337.
- [56] DAFM, 'Food Vision 2030', Department of Agriculture, Food and the Marine, Jul. 2021. [Online]. Available: https://assets.gov.ie/179717/910771f6-05ed-43f1-b8ce-52ef7c602710.pdf
- [57] Ireland, 'CLIMATE ACTION PLAN 2021 Securing Our Future', Government of Ireland, Nov. 2021. [Online]. Available: https://assets.gov.ie/203546/a183a324-40ed-49c9-b630-bab0fbdd2ce2.pdf

- [58] B. McMullin and P. Price, GHG-WE: spreadsheet models for 'cumulative warming equivalent' analysis of mixed greenhouse gas emission pathways (Version 1.0). Zenodo, 2020. [Online]. Available: http://doi.org/10.5281/zenodo.3974485
- [59] B. McMullin, M. B. Jones, P. R. Price, A. McGeever, and P. Rice, 'IE-NETs: Investigating the Potential for Negative Emissions Technologies (NETs) in Ireland', Environmental Protection Agency, EPA Research Report 354, Nov. 2020. Accessed: Nov. 10, 2020. [Online]. Available: https://www.epa.ie/publications/research/climate-change/Research Report 354.pdf
- [60] G. Grassi et al., 'Critical adjustment of land mitigation pathways for assessing countries' climate progress', Nat. Clim. Change, vol. 11, no. 5, Art. no. 5, May 2021, doi: 10.1038/s41558-021-01033-6.
- [61] L. Chancel and T. Piketty, 'Carbon and inequality: from Kyoto to Paris', p. 50, 2015.
- [62] M. Sharmina et al., 'Decarbonising the critical sectors of aviation, shipping, road freight and industry to limit warming to 1.5–2°C', Clim. Policy, vol. 0, no. 0, pp. 1–20, Oct. 2020, doi: 10.1080/14693062.2020.1831430.
- [63] EPA, 'IE GHG Projections Technical Report 2021', Environmental Protection Agency (Ireland), 2021. [Online]. Available: https://reportnet.europa.eu/public/dataflow/113
- [64] D. H. Daly, A. Matthews, B. McMullin, and P. Price, 'The role of agriculture emissions in Irish and global climate mitigation pathways', Policy advisory, 2021.
- [65] T. Kenny, M. Cronin, and C. Sage, 'A retrospective public health analysis of the Republic of Ireland's Food Harvest 2020 strategy: absence, avoidance and business as usual', Crit. Public Health, vol. 28, no. 1, pp. 94–105, Jan. 2018, doi: 10.1080/09581596.2017.1293234.
- [66] T. Donnellan, K. Hanrahan, J. P. Breen, and P. Gillespie, 'Climate Change and Agricultural Policy Coherence: Agricultural Growth and GHG Emissions in Ireland', Apr. 2013. [Online]. Available: https://econpapers.repec.org/scripts/redir.pf?u=https%3A%2F%2Fageconsearch.umn.edu%2Frecord%2F158853%2Ffiles%2FKevin_Hanrahan_Donnellan_Hanrahan_Breen_gillespie_AES_2013.pdf;h=repec:ags:aesc13:158853
- [67] D. McLaren and N. Markusson, 'The co-evolution of technological promises, modelling, policies and climate change targets', Nat. Clim. Change, vol. 10, no. 5, Art. no. 5, May 2020, doi: 10.1038/s41558-020-0740-1.
- [68] J. C. Minx et al., 'Negative emissions—Part 1: Research landscape and synthesis', Environ. Res. Lett., vol. 13, no. 6, p. 063001, 2018, doi: 10.1088/1748-9326/aabf9b.
- [69] P. Smith et al., 'Biophysical and economic limits to negative CO₂ emissions', Nat. Clim. Change, vol. 6, pp. 42–50, Dec. 2015, doi: 10.1038/nclimate2870.
- [70] S. Fuss et al., 'Negative emissions—Part 2: Costs, potentials and side effects', Environ. Res. Lett., vol. 13, no. 6, p. 063002, Jun. 2018, doi: 10.1088/1748-9326/aabf9f.
- [71] W. Rickels, C. Merk, F. Reith, D. Keller, and A. Oschlies, '(Mis)conceptions about modelling of negative emissions technologies', Environ. Res. Lett., Aug. 2019, doi: 10.1088/1748-9326/ab3ab4.
- [72] C. Pozo, Á. Galán-Martín, D. M. Reiner, N. Mac Dowell, and G. Guillén-Gosálbez, 'Equity in allocating carbon dioxide removal quotas', Nat. Clim. Change, vol. 10, no. 7, Art. no. 7, Jul. 2020, doi: 10.1038/s41558-020-0802-4.
- [73] O. Rueda, J. M. Mogollón, A. Tukker, and L. Scherer, 'Negative-emissions technology portfolios to meet the 1.5 °C target', Glob. Environ. Change, p. 102238, Feb. 2021, doi: 10.1016/j.gloenvcha.2021.102238.